



2026

Site Specific HSE Plan

AMAZON SHV-150

**Safety Department
Corporate Offices**

**9640 WALLACE LAKE RD.
SHREVEPORT, LA 71136**

Phone (318) 688-0610

Fax (318) 688-4998

***“A company committed to safety
excellence”***

Each employee at this worksite shall have this Site Specific HSE Plan (SSHP) explained during their safety orientation. All staff shall follow its provisions. Revisions are strongly encouraged by all personnel. Please advise the Safety Manager of any areas that need changing – you are the one performing the work and best know the hazards that can be encountered.

SAFETY POLICY

Management is committed to providing its employees with the safest and healthiest work environment possible. The purpose and goal of the health and safety program is to provide a positive working environment and an injury-free workplace for all employees.

Managers and Supervisors are responsible for:

- ensuring hazards are identified and appropriately controlled,
- creating an environment that promotes active employee participation in health and safety-related activities, and
- ensuring that health and safety-related initiatives are adequately resourced.

Employees are responsible for:

- working safely,
- ensuring their co-workers are protected and work safely,
- assisting in the identification of health and safety issues and concerns, and
- participating in activities or programs initiated by Turner Construction Company that enhance health and safety.

Contractors are responsible for:

- working safely,
- complying with all municipal policies regarding contract instructors,
- assisting in the identification of health and safety issues and concerns, and
- participating in activities or programs initiated by Turner Construction Company that enhance health and safety.

This policy is to be posted in all WICKER CONSTRUCTION, INC. facilities by the site supervisor.

ENVIRONMENTAL POLICY

WICKER CONSTRUCTION, INC. recognizes that environmental concerns are of critical importance. We encourage our employees to join with the Wicker Construction, Inc. in full acceptance of and compliance with this policy.

We will create procedures that fully comply with federal, state and local regulations. We will provide adequate training to our employees to ensure our workers are aware of these procedures and are capable of following them.

Protection of the Environment

We will employ practical measures to protect the environment. We will conserve and protect the water, air, and land resources we use. We will strive to eliminate any releases to land, air or water that may

harm human health or the environment. Continuous improvement in our environmental performance will be a principal objective.

Waste Management Policy Statement

We will work to prevent waste and pollution at the source whenever possible. New facilities and improvements of existing operations will use processes designed to minimize the environmental effects of our operations and will incorporate functional pollution control equipment.

Recycling and Waste Disposal

We will support recycling programs where practical and will use environmentally safe treatment and disposal practices for waste that is not eliminated at the source or recycled.

Compliance

We will manage existing facilities so that we meet or exceed legal requirements. We will implement programs and procedures to satisfy compliance. We will conduct compliance audits and monitor procedures and practices to evaluate our performance.

Disclosure

We will inform our employees of our progress in environmental issues. We will cooperate with the authorities and regulatory agencies in responding to inquiries. We will encourage our employees to report to Wicker Construction, Inc. conditions that they reasonably believe could be harmful to the environment or pose health or safety hazards so the Wicker Construction, Inc. can initiate prompt corrective actions.

This policy is to be posted in all WICKER CONSTRUCTION, INC. facilities by the site supervisor.

INCIDENTS AND INVESTIGATIONS

The following must be reported to the employee's supervisor immediately. If that person is not available then the WICKER CONSTRUCTION, INC. Safety Manager shall be immediately notified for:

- Near miss incidents with the potential to harm people, the environment, or assets;
- Work related injuries or illnesses;
- Property damage including vehicle incidents;
- Hazardous chemical spillage, loss of containment and contamination;

All injuries must be reported to the WICKER CONSTRUCTION, INC. Safety Manager. In the case of a major injury or incident

the scene of the event should be closed off and kept "as is" at the time of the incident. This is vital for effective incident investigation.

DISCIPLINARY SYSTEM

It is the responsibility of each and every person employed by WICKER CONSTRUCTION, INC. to work in a safe and efficient manner. The safety system provides guidelines and procedures to help ensure that safe work practices are observed. In the event that any employee violates provisions of the WICKER CONSTRUCTION, INC. safety system or works in a manner that threatens his own health and safety or the health and safety of the employees around him, he will be subject to disciplinary action.

COMPETENT PERSON

OSHA standards require that employers inspect trenches daily and as conditions change by a competent person before worker entry to ensure elimination of excavation hazards. A competent person is an individual who can identify existing and predictable hazards or working conditions that are hazardous, unsanitary, or dangerous to workers along with classifying which soil type in which they will be working with.

HAZARDOUS CHEMICALS

Hazardous chemicals present at sites are described in SDS's available to employees as part of the WICKER CONSTRUCTION, INC. safety program. No hazardous chemical may be used without the proper SDS being reviewed. No chemicals can be taken on a client job site without their permission.

SAFE WORK PRACTICES

Additional work practices are contained in the site specific HSE plans based on local operating requirements. Key safe work practices include:

- It is the responsibility of each employee to perform his or her job in accordance with the requirements of the WICKER CONSTRUCTION, INC. Safety & Health Management System, the local WICKER CONSTRUCTION, INC. Site Specific HSE Plan and client safety requirements.
- No equipment shall be operated unless the employee has received proper training by the supervisor.
- Tools and equipment damaged during use must be replaced or repaired only by a qualified person or Wicker Construction, Inc.
- As tasks are completed, or at the end of each work shift time is allowed for cleanup of tools, debris, etc. to keep the site clean and free of accumulated debris.

DRIVING SAFETY

Operators of WICKER CONSTRUCTION, INC. or client vehicles shall be qualified by possession of a valid, current driver's license for the type of vehicle being driven. Employees driving requirements include:

- Obey all driving laws or regulations as well as requirements of clients;
- Immediately report any citation, warning, vehicle damage or near miss associated with Wicker Construction, Inc. or client vehicle operation to the supervisor;
- Immediately report any restriction or change to their driving privileges to the supervisor.
- Seat belts shall always be worn by all occupants during the operation of any vehicle;
- Defensive drivers continually assess conditions and hazards and remain prepared for any challenge that may approach them;
- Avoid backing when possible, by planning ahead. Always back up with the minimum amount of space needed. If backing, use a spotter or get out of the vehicle and ensure you have a clear path;
- When speaking with a passenger, always keep your eyes on the road;
- Drive for conditions, not just the speed limit;
- Alcohol or illegal drugs are not allowed to be in a Wicker Construction, Inc., client or leased vehicle at any time.

PERSONAL PROTECTIVE EQUIPMENT

Eye and Face Protection

Employees must use appropriate eye or face protection when exposed to eye or face hazards from flying particles, molten metal, liquid chemicals, acids or caustic liquids or chemical gases or vapours.

Head Protection

Employees must wear protective helmets when working in areas where there is a potential for injury to the head from employee-initiated impact or impact from falling or other moving objects.

Foot Protection

Employees must wear protective footwear when working in areas where there is a danger of foot injuries.

Hand Protection

Employees must wear the proper type of gloves based on the hazard – cotton gloves offer no protection against chemicals.

Fall Protection

Fall protection must be provided when employees are exposed to a vertical fall of six feet or more over a lower level.

Fall Protection

Applies to all Wicker employees who have work assignments at work levels that exceed 6 feet in height where guardrails or nets are not utilized. This includes work near and around excavations. Guardrails, safety nets, or personal fall arrest systems shall be used where feasible. When work is performed on a non-owned or operated site, the operator's program shall take precedence, however, this document covers Wicker employees and shall be used on owned premises, or when an operator's program doesn't exist or is less stringent.

ELECTRICAL SAFETY

- Report any electrical problems to WICKER CONSTRUCTION, INC. immediately
- Never try to fix equipment – you are not AUTHORIZED nor TRAINED to do so.
- Avoid contact with energized conductors
- Avoid overloading circuits
- Avoid contact with high voltage equipment
- Do not use damaged equipment
- Electrical panels shall not be blocked (3' clearance)
- NEVER try to defeat or bypass a locked or tagged piece of equipment! Do not touch any tags or locks.
- Use approved lighting in wet areas and classified areas

Extension cords are considered temporary wiring and shall not be used for permanent installations and not plugged into each other.

HOW TO LIFT AND CARRY

Manual material handling is one of the more common activities you carry out on WICKER CONSTRUCTION, INC. contract. Lifting and carrying can be done without injury by following these simple guidelines:

Size up the load: If a load is over 50 lbs or bulky, or the floor is uneven or slippery GET HELP! If you are uncomfortable lifting less than 50 lbs by yourself, break the load down into smaller loads or get help.

Lift it right:

- Put one foot alongside the object, and one foot behind it. Keep your feet shoulder width apart.
- Assume the weight lifters position. Head up, backside out, chest in, keep your back vertical, and avoid twisting or flexing side to side.
- Get a good, firm grip using your palms instead of your fingers, which are weaker.
- Keep the load close to your body and check your balance.

- Lift straight up using the power in your legs.
- Avoid twisting as you turn with a load, shift your feet instead. If you intend to turn, point the forward foot in the direction of the turn.
- Never lift something waist level in one motion.
- Avoid lifting anything over 20 lbs over shoulder height.
- To set a load down NEVER bend from the waist; use your legs, keep your back straight and hold your head up.

TRENCH SAFETY MEASURES

Trenches 5 feet (1.5 meters) deep or greater require a protective system unless the excavation is made entirely in stable rock. If less than 5 feet deep, a competent person may determine if a protective system is required or not.

GENERAL TRENCHING AND EXCAVATION RULES

"AN UNPROTECTED TRENCH IS AN EARLY GRAVE"

Cave-ins pose the greatest risk and are much more likely than other excavation-related accidents to result in worker fatalities. Other potential hazards include falls, falling loads, hazardous atmospheres, and incidents involving mobile equipment. One cubic yard of soil can weigh as much as a car. Other basic trench rules include:

- Keep heavy equipment away from trench edges
- Identify other sources that might affect trench stability
- Keep excavated soil (spoil) and other material at least 2 feet (0.6 meters) from trench edges
- Know where underground utilities are before digging
- Test for atmospheric hazards such as low oxygen, hazardous fumes and toxic gases when greater than 4' deep
- Inspect trenches at the start of each shift
- Inspect trenches following a rainstorm or other water intrusion
- Do not work under suspended or raised loads and materials
- Inspect trenches after any occurrence that could have changed conditions in the trench
- Ensure that personnel wear high visibility or other suitable clothing when exposed to vehicular traffic
- Must have safe access and egress to all excavations including ladders, steps, ramps, or other safe means of exit for employees working in trenches 4' or deeper
- Ladders must be placed within 25 feet of all workers

Shreveport, LA 71103

318-212-4000

PROTECTIVE SYSTEMS

BENCHING- a method of protecting workers from cave-ins by excavating the sides of an excavation to form one or a series of horizontal steps, usually with vertical or near vertical surfaces between levels. Type C soil **CAN NOT** be benched!

SLOPING- involves cutting back the trench wall at an angle inclined away from the excavation.

SHORING- requires installing aluminum hydraulic or other types of supports to prevent soil movement and cave-ins.

SHIELDING- protects workers by using trench boxes or other types of supports to prevent soil cave-ins. Designing a protective system can be complex because you must consider many factors: soil classification, depth of cut, water contact of soil, changes caused by weather or climate, surcharge loads (e.g. spoil, other materials to be used in the trench) and other operations in the vicinity.

EMERGENCY ACTION PLAN

The purpose of this Emergency Response Plan is to advise of emergency procedures to protect life, minimize danger of exposure to personnel and to protect property at client facilities. This Plan shall apply to all WICKER CONSTRUCTION, INC. staff, subcontractors and their visitors to the WICKER CONSTRUCTION, INC. facility.

Any accident or injury must be reported immediately through the following channels:

- 1) **Project Safety Supervisor- Tim Politz 318-573-3948**
- 2) **Site Safety Rep.- Brian Shoup 318-272-1984**
- 3) **Crew/Division Leader- David Helms 318-207-2717**
- 4) **Lead Project Manager-Lance Sanders 318-364-6606**

The nearest hospital to the project location is in Shreveport, LA and is 20 miles from the jobsite. The address of this facility is:

Willis Knighton Medical Center (North Campus)

2600 Greenwood Rd

The Project Safety Manager will make the decision on the best course of action to treat each injury. If an injury is determined to be critical in the opinion of the employee's immediate supervisor, the supervisor must **call 911 immediately** before calling the Safety Manager to report the accident.

PROJECT CONTACTS

Project Safety Supervisor- Tim Politz 318-573-3948

Site Safety Rep.- Brian Shoup 318-272-1984

Crew/Division Leader- David Helms 318-207-2717

Lead Project Manager- Lance Sanders 318-364-6606

Project Manager- Avere Doles 318-272-8440

Project Manager- Connor Branch 318-557-2203

Fleet Manager- Travis Morton 409-489-3482

